

## Test Cells

## **Hydrostatic and Gas Testing**



ISE has a comprehensive hydrostatic pressure test facility including temperature, flow loop and hyperbaric testing.

The 4-off test cells are capable of hydraulic or gas testing with cameras to allow safe remote, and off-site, observation of all testing.

Stackable water bath sections may be used to fully submerge valves during testing thereby providing the highest level of scrutiny.

- □ Gas Testing up to 20 ksi MWP (137.9 MPa)
- Data Acquisition, up to 16 Channels
- ▶ Wide range of Test Standard capabilities, including API 17G

Test Cell 1	
Dimensions	L70" x B71" x H95" (L1.788 m x B1.803 m x H2.413 m)
Hydraulic Lines 1	2x 3/8" MP Autoclave, 10,000 psi MWP (68.9 MPa)
Hydraulic Lines 2	3x 1/4" HP Autoclave, 25,000 psi MWP (172.4 MPa)
Gas Lines	2x 3/8" MP Gas Line Manifold, 20,000 psi MWP (137.9 MPa)
Auxiliary Inlet	4x 3/8" MP Autoclave, 20,000 psi MWP (137.9 MPa)
Auxiliary Line	1x 3/8" HP Autoclave, 30,000 psi MWP (206.8 Mpa)

Test Cell 2	
Dimensions	L147" x B142" x H120" (L3.734 m x B3.606 m x H3.048 m)
Hydraulic Lines 1 & 2	2x 3/8" MP Autoclave, 10,000 psi MWP (68.9 MPa)
Hydraulic Lines 3 & 4	2x 3/8" MP Autoclave, 15,000 psi MWP (103.4 MPa)
Gas Lines	2x 3/8" HP Gas Line Manifold, 30,000 psi MWP (206.8 MPa)

Test Cell 3	
Dimensions	L98" x B90" x H90" (L2.489 m x B2.286 m x H2.286 m)
Hydraulic Lines 1 & 2	2x 3/8" MP Autoclave, 10,000 psi MWP (68.9 MPa)
Hydraulic Lines 3 & 4	2x 3/8" MP Autoclave, 15,000 psi MWP (103.4 MPa)
Gas Lines	2x 3/8" HP Gas Line Manifold, 30,000 psi MWP (206.8 MPa)

Test Cell 4	
Dimensions	L48" x B46" x H80" (L1.168 m x B1.219 m x H2.032 m)
Hydraulic Lines	4x 3/8" MP Autoclave, 10,000 psi MWP (68.9 MPa)
Gas Lines	2x Gas Line Manifold, 20,000 psi MWP (137.9 MPa)

